

ESTIMATE



Chris Dingus

3103 Hillman-Ford Road, Morral, OH,
Morral, OH 43337

Steep Master Roofing LLC

11144 Plattsburg Rd
South Charleston, Ohio 45368
Phone: (937) 568-2028
Email: steepmasterroofing@gmail.com
Web: steepmasterroofing.com

Estimate # 002227
Date 03/30/2022

| Description | Total |
|---|------------|
| Rebuild 1 row of 8" center scored concrete block on 1 masonry chimney. Tuckpoint as needed. | \$4,879.99 |
| Rebuild top 3 coarse of chimney liner brick as needed. | \$0.00 |
| Demo the exterior brick of chimney as needed.. | \$0.00 |
| Pour a formed fiber reinforced concrete crown. | \$0.00 |
| Build and remove scaffolding system. | \$0.00 |
| Repair list for pictures 1- 28 as followed below. | \$0.00 |
| Tuckpoint all joints with type N Mortar. | \$0.00 |
| Remove existing mortar to allow for repointing. | \$0.00 |
| Brick replacement as needed. | \$0.00 |
| Sure Kleen 600 cleaner. | \$0.00 |
| Apply Siloxane PD water repellent. | \$0.00 |
| Apply and remove protective roof mats daily. | \$0.00 |
| Apply new sealant and fasteners as needed. | \$0.00 |

| | |
|---|--------|
| Install and remove safety roof jacks and worksite protection. | \$0.00 |
| All materials included, full clean up and haul away debris. | \$0.00 |
| 1 Year Workmanship Warranty. | \$0.00 |

| | |
|-----------------|-------------------|
| Subtotal | \$4,879.99 |
| Total | \$4,879.99 |

Payment Schedule

| | |
|--------------------|------------|
| 1st payment (100%) | \$4,879.99 |
|--------------------|------------|

Notes:

10% cancellation fee.
Property owner supplies water and electric source.
Not responsible for landscaping damage.

\$4879.99 dollars are due immediately upon completion.

Recommendations: Chimney cap to keep animals/ rain water from entering chimney. Apply water repellent to all brick and block surfaces to preserve any further damage.

By signing this document, the customer agrees to the services and conditions outlined in this document.

Chris Dingu